

DETECTOR TEST PANEL FRONT VIEW



DETAIL A **TYPICAL VERTICAL SECTION DETAIL**



DD50 D-SUB CONNECTOR PINS

PLUG (MALE) CONNECTOR SHOWN ~
MIRROR FOR SOCKET (FEMALE) CONNECTOR ~
SEE NOTE 2

NOTES

1. Upper and lower channel identification labels shall match the detector channels shown in the Contract Plans.
2. Connectors **DT3S**, **DT3P**, **DT4S**, and **DT4P** are **Type DD50 D-Sub** connectors with pin layouts and assignments as shown. The suffix "**S**" indicates a socket (female connector) and the suffix "**P**" indicates a plug (male connector).
3. **Detector Termination Interface Panel** terminals not shown due to variations in arrangement and numbering between manufacturers.
4. Connectors **DT3P** and **DT4S** shall be installed in one of the following arrangements:

   a) Mounted to the back of the **Detector Test Panel**. Connectors shall use a spring latch (bail) to secure the connection.

   b) Mounted on a cable, within six inches of the back of the **Detector Test Panel**. Connectors shall use thumb-screws to secure the connection.
5. Connectors **DT3S** and **DT4P** shall be designed such that they can be connected directly, bypassing the **Detector Test Panel**.
6. The **Detector Termination Interface Panel** shall be installed electrically between the **Detector Test Panel** and the **C1** connector. A second additional terminal block may be installed electrically between the **Input File(s)** and the **Detector Test Panel**.
7. Test switches shall be three position switches with the "**Test**" position being a momentary contact with spring return to the "**OFF**" position. Test switch position functions shall be as described in **Standard Specification section 9-29.13(10)**.
8. Location of the **Display On/Off** switch is approximate. This switch shall be located to the right of all of the individual channel test switches and clear of the mounting rack.

FUNCTIONAL BLOCK DIAGRAMS



CONNECTOR PIN ASSIGNMENTS (SEE NOTE 3)

CONNECTOR DT3S

PIN	CONNECT TO	FUNCTION	PIN	CONNECT TO	FUNCTION
1	I-1F	DET. 1	26	J-3F	DET. 23
2	I-2F	DET. 3	27	J-4F	DET. 25
3	I-3F	DET. 5	28	J-5F	DET. 27
4	I-4F	DET. 7	29	J-2W	DET. 22
5	I-1W	DET. 2	30	J-3W	DET. 24
6	I-2W	DET. 4	31	J-4W	DET. 26
7	I-3W	DET. 6	32	J-5W	DET. 28
8	I-4W	DET. 8	33	J-6F	DET. 29
9	I-5F	DET. 9	34	J-7F	DET. 31
10	I-6F	DET. 11	35	J-8F	DET. 33
11	I-7F	DET. 13	36	J-9F	DET. 35
12	I-8F	DET. 15	37	J-6W	DET. 30
13	I-5W	DET. 10	38	J-7W	DET. 32
14	I-6W	DET. 12	39	J-8W	DET. 34
15	I-7W	DET. 14	40	J-9W	DET. 36
16	I-8W	DET. 16	41	NC	NA
17	I-9F	DET. 17	42	NC	NA
18	I-12F	Ø2 PED	43	NC	NA
19	I-13F	Ø6 PED	44	NC	NA
20	J-1F	DET. 19	45	NC	NA
21	I-9W	DET. 18	46	NC	NA
22	I-12W	Ø4 PED	47	NC	NA
23	I-13W	Ø8 PED	48	NC	NA
24	J-1W	DET. 20	49	I15-1	POWER
25	J-2F	DET. 21	50	I15-2	GROUND

CONNECTOR DT3P

PIN	CONNECT TO	FUNCTION	PIN	CONNECT TO	FUNCTION
1	I1U - IN		26	J3U - IN	
2	I2U - IN		27	J4U - IN	
3	I3U - IN		28	J5U - IN	
4	I4U - IN		29	J2L - IN	
5	I1L - IN		30	J3L - IN	
6	I2L - IN		31	J4L - IN	
7	I3L - IN		32	J5L - IN	
8	I4L - IN		33	J6U - IN	
9	I5U - IN		34	J7U - IN	
10	I6U - IN		35	J8U - IN	
11	I7U - IN		36	J9U - IN	
12	I8U - IN		37	J6L - IN	
13	I5L - IN		38	J7L - IN	
14	I6L - IN		39	J8L - IN	
15	I7L - IN		40	J9L - IN	
16	I8L - IN		41	NC	NA
17	I9U - IN		42	NC	NA
18	I12U - IN		43	NC	NA
19	I13U - IN		44	NC	NA
20	J1U - IN		45	NC	NA
21	I9L - IN		46	NC	NA
22	I12L - IN		47	NC	NA
23	I13L - IN		48	NC	NA
24	J1L - IN		49	+24 VDC	POWER
25	J2U - IN		50	LOGIC GND	GROUND

CONNECTOR DT4S

PIN	CONNECT TO	FUNCTION	PIN	CONNECT TO	FUNCTION
1	I1U - OUT		26	J3U - OUT	
2	I2U - OUT		27	J4U - OUT	
3	I3U - OUT		28	J5U - OUT	
4	I4U - OUT		29	J2L - OUT	
5	I1L - OUT		30	J3L - OUT	
6	I2L - OUT		31	J4L - OUT	
7	I3L - OUT		32	J5L - OUT	
8	I4L - OUT		33	J6U - OUT	
9	I5U - OUT		34	J7U - OUT	
10	I6U - OUT		35	J8U - OUT	
11	I7U - OUT		36	J9U - OUT	
12	I8U - OUT		37	J6L - OUT	
13	I5L - OUT		38	J7L - OUT	
14	I6L - OUT		39	J8L - OUT	
15	I7L - OUT		40	J9L - OUT	
16	I8L - OUT		41	NC	NA
17	I9U - OUT		42	NC	NA
18	I12U - OUT		43	NC	NA
19	I13U - OUT		44	NC	NA
20	J1U - OUT		45	NC	NA
21	I9L - OUT		46	NC	NA
22	I12L - OUT		47	NC	NA
23	I13L - OUT		48	NC	NA
24	J1L - OUT		49	NC	NA
25	J2U - OUT		50	NC	NA

CONNECTOR DT4P

PIN	CONNECT TO	FUNCTION	PIN	CONNECT TO	FUNCTION
1	C1 - 56	DET. 1	26	C1 - 64	DET. 23
2	C1 - 39	DET. 3	27	C1 - 48	DET. 25
3	C1 - 63	DET. 5	28	C1 - 57	DET. 27
4	C1 - 47	DET. 7	29	C1 - 44	DET. 22
5	C1 - 56	DET. 2	30	C1 - 77	DET. 24
6	C1 - 43	DET. 4	31	C1 - 48	DET. 26
7	C1 - 76	DET. 6	32	C1 - 57	DET. 28
8	C1 - 47	DET. 8	33	C1 - 42	DET. 29
9	C1 - 58	DET. 9	34	C1 - 66	DET. 31
10	C1 - 41	DET. 11	35	C1 - 50	DET. 33
11	C1 - 65	DET. 13	36	C1 - 59	DET. 35
12	C1 - 49	DET. 15	37	C1 - 46	DET. 30
13	C1 - 58	DET. 10	38	C1 - 79	DET. 32
14	C1 - 45	DET. 12	39	C1 - 50	DET. 34
15	C1 - 78	DET. 14	40	C1 - 61	DET. 36
16	C1 - 49	DET. 16	41	NC	NA
17	C1 - 60	DET. 17	42	NC	NA
18	C1 - 67	Ø2 PED	43	NC	NA
19	C1 - 68	Ø6 PED	44	NC	NA
20	C1 - 55	DET. 19	45	NC	NA
21	C1 - 62	DET. 18	46	NC	NA
22	C1 - 69	Ø4 PED	47	NC	NA
23	C1 - 70	Ø8 PED	48	NC	NA
24	C1 - 55	DET. 20	49	NC	NA
25	C1 - 40	DET. 21	50	NC	NA

PIN TABLE EXAMPLES:

J1F: Input File J, Slot 1, Terminal F

DET. 14: Detector #14

I9U - IN: Detector Test Panel Position I9, Upper Channel, Input Terminal

C1 - 58: C1 Connector, Pin 58

N/A: Not Applicable

NC: Not Connected

MATTHEW J. NEELEY STATE OF WASHINGTON 46597 REGISTERED PROFESSIONAL ENGINEER

Neeley, Matthew
Jun 18 2018 8:15 AM
cosign

TYPE 332 SIGNAL CABINET DETECTOR TEST PANEL

STANDARD PLAN J-80.15-00

SHEET 1 OF 1 SHEET

APPROVED FOR PUBLICATION
Carpenter, Jeff
Jun 28 2018 10:30 AM
cosign
STATE DESIGN ENGINEER
Washington State Department of Transportation

DRAWN BY: BILL BERENS